BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2016-17/RD/WORK_INDENT24277

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017

Improvements of drains and roads near A.S.Hanumayya house and surroundings Byatrayanapura in ward no.07, byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N VENKATA REDDY	
				In Figures	In Words
1	290.03	KSRB 2-2.2:Earth work excavation for foundation of building, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ORDINARY soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches , stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications and direction of the Engineer-in-charge.	Cum	83.16	Rupees Eighty Three and Sixteen Paise Only
2	133.24	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification .	Cum	5070.6	Rupees Five Thousand Seventy and Sixty Paise Only
3	29.44	KSRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications.	Cum	5490.72	Rupees Five Thousand Four Hundred Ninety and Seventy Two Paise Only
4	14.85	KSRB 4.2.2: Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastizers @ 3lts confirming to IS 9103-1999 RE affirmed - 2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, stair case lintels, retaining walls return walls, walls(anythickness) including attached plasters columns piers abutments pillars posts struts butresses string or lacing courses parapets copings, bed blocks , plain windows cills fillets etc., including cost of all materials labour HOM of machinery curing complete as per specifications.	CUM	6198.12	Rupees Six Thousand One Hundred Ninety Eight and Twelve Paise Only
5	0.89	KSRB 4-.9-2:Providing and fabricating TMT . Steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking,placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design(laps and wasteage shall not measured and paid) cost of materials. labour. HOM of machinery complete as per specifications . (Page NO 17, Itm. NO. 4.46.2)	tonne	59327.91	Rupees Fifty Nine Thousand Three Hundred Twenty Seven and Ninety One Paise Only
6	132	KSRB 4-6.4: Providing and removing centering, shuttering strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness including attached pilasters, buttressed, plinth and string courses cost of all materials, labour complete as per specifications	Sqm	306.72	Rupees Three Hundred Six and Seventy Two Paise Only
7	89.15	KSRB 4-48: Providing and laying in cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for RCC works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complate (exclusive of cost of steel and fabrication charges	Cum	4425.0	Rupees Four Thousand Four Hundred Twenty Five Only
8	1.05	KSRB 5.3-1:Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms hign, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications.	Cum	3456.0	Rupees Three Thousand Four Hundred Fifty Six Only
9	11.7	KSRB 5.3-1:Providing ruled pointing of course stone msonry with cement mortar 1:3 20 mm deep, after raking joints to depth of 20 mm nicley lining, including cost of materials, labour, curing etc., complete as per specifications and directions of the engineer-in-charge.	Sqm	35.64	Rupees Thirty Five and Sixty Four Paise Only

Signature of the contractor

Executive Engineer

No.	Approved Qty.	Description	Unit	Approved Tender Rates of N VENKATA REDDY	
				In Figures	In Words
10	73.8	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications	Sqm	1836.0	Rupees One Thousand Eight Hundred Thirty Six Only
11	135	Supplying and fixing M.S.Rectangular poles made out of 2 equals angles 65*65*6 mm welded together and fixed in CC (1:2:4) with 2 nos 16mm dia M.S.Hold fast roads each of lengt 25cmc, Inlcuding cost of all materials cutting, bendng scaffoliding wherever necessary, nicely finishing the welded joints with all leads lifts and as per the direction of the Engineer-in-charge of the work and including providing 2coats of approved quality paint over one coat of shop painting.	M	973.08	Rupees Nine Hundred Seventy Three and Eight Paise Only
12	60	KSRB 8.3-2: Providing and fixing require line and slope roofing with semi corrugated PVC roofing sheets of industrial profile 250/40 in 2.00mm thick white colour, fire and heat resistant having width of 1.054 mts, fixed with self tapping screws with washers, over the existing purlins, rafters and self tapping screws with washers, over the exisiting purlins, rafters and trusses including cost of materials, labour, complete as per specfications.	Sqm	901.0	Rupees Nine Hundred One Only
13	13.5	KSRB 14.10.3: Providing flooring with 20mm thick polished cadapa slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to lineand level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per speciifcations.	Sqm	1129.96	Rupees One Thousand One Hundred Twenty Nine and Ninety Six Paise Only
14	290.03	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification	Cum	94.82	Rupees Ninety Four and Eighty Two Paise Only

Signature of the Contractor

08/03

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

08/03